





(1978) PUBL.

SD 7437



B © Crown copyright 1978


COMPILATION DATA



1:12500 scale * 1:1250 scale (photographically reduced)
 (a) Surveyed.
 (b) Reconstructed from former County Series plans and revised.
 (c) Revised.

Surveys of changes since the publication of this plan may be available. Enquiries should be addressed to the Director General or to the local Ordnance Survey office.

HEIGHTS are given in METRES above the Newlyn Datum.
 Bench mark lists, which may contain later levelling information and particulars of bench marks to which no values have been shown, are obtainable from the Director General, Ordnance Survey.
 The representation on this plan of a road, track or path is no evidence of the existence of a right of way.
 The alignment of tunnels where shown is approximate.
 Details of symbols and abbreviations used can be obtained from Ordnance Survey, Southampton.



BOUNDARIES

ENGLAND & WALES		SCOTLAND	
County	Region or Islands Area	County	Region or Islands Area
District	District	District	District
London Borough	Not shown	District	District
Civil Parish (England)	Not shown	District	District
Community (Wales)	Not shown	District	District
Electoral Division	Electoral Division	District	District
Ward	Ward	District	District
Constituency (Co or Boro)	Constituency (Co or Boro)	District	District

Coincident boundaries are shown by the first appropriate symbol above, e.g. * Boro Const & E D Bdy
 For Ordnance Survey purposes County Boundary is deemed to be the limit of the parish structure whether or not a parish area adjoins.

Boundary markings

B.B.	Base of Bank	C.R.	Centre of Road, etc.	F.F.	Face of Fence	T.B.	Top of Bank
C.B.	Centre of Bank	C.S.	Centre of Stream, etc.	F.W.	Face of Wall	T.H.	Track of Hedge
C.C.S.	Centre of Covered Stream	Def.	Defence	R.H.	Roof of Hedge	T.S.	Track of Stream
C.D.	Centre of Drain, etc.	E.K.	Edge of Kerb	S.R.	Side of River, etc.	Und.	Undefined

Imperial equivalents for metric boundary markings
 0.91m = 3ft 1.22m = 4ft

Made and published by the Director General of the Ordnance Survey, Southampton.

AREAS
Area measurement is to plan edge only.
The number and area, in hectares (ha) and acres, is shown within each parcel of land.

EXAMPLE: 4267..... parcel number
 1.809ha..... area in hectares
 4.47..... area in acres
 When identifying a parcel it is important to specify the number of the plan on which it falls.
 Enclosures or features joined for measurement of area.....
 Limit of area within which individual parcels are not shown.....
 To convert hectares to acres multiply by 2.471 05
 To convert acres to hectares multiply by 0.404 69

NATIONAL GRID REFERENCE

The grid lines form part of the National Grid and are at 100 metre intervals. To give a unique reference defining the position of a point to within 10 metres proceed as follows:-

- Take the two letters preceding the sheet number..... TQ
- Take the west edge of the grid square in which the point lies and read the figures opposite this line on the north or south margin..... 058
Estimate tens of metres from the grid line to the point (distance e)..... 8
The resulting four figure number is the Easting..... 0588
- Take the south edge of the grid square in which the point lies and read the figures opposite this line on the east or west margin..... 291
Estimate tens of metres from the grid line to the point (distance n)..... 6
The resulting four figure number is the Northing..... 2916
- The full ten metre reference is given by writing first the letters, followed by the Easting and then by the Northing..... TQ 05882916

For further information see 'An Introduction to the Projection for Ordnance Survey Maps and the National Reference System.'

